

STEEL FIXING

RA NO

DATE

H.T.I Score 5	Low Risk-Regular Monitoring	
Contract		
Persons involved in RA	Name	Signatures
Foreman		
Second Foreman		
Safety Officer		
Representative		

Documentation Required	Training Required	PPE and Safety Equipment Required
OHS Act and Construction Regulations	General induction - all employees	Long Trousers
Appointment 6(1)	Toolbox talks	Safety Footwear
Appointment First Aider	First Aider	Eye Protection
Competency First Aider		Gloves

	Activity Steps	Hazards and Risks	Preventative Measures	Rating
1	Delivery and stacking of material	Inefficient stacking. Poor housekeeping. Sharp edges, protrusions and snags. Lost productivity, injuries to persons-cuts, bruises, puncture wounds.	Stacking and storage supervisor ensures efficient and safe stacking. Daily tidying of stored materials. Protective gloves to be worn.	5
	Movement of material from storage are to work area	Sharp edges, protrusions and snags. Uneven ground.Obstacles on path. Injuries to persons-cuts, bruises, puncture wounds. Trip/ fall injuries.	Protective gloves to be worn. Create level walkway to work area. Remove obstacles from path.	5
3	Tying steel	Sharp edges, protrusions and snags. Steel/ wire off cuts. Injuries to persons-cuts, bruises, puncture wounds.	Protective gloves to be worn. Good housekeeping to be maintained at all times. Daily removal of steel/ wire off cuts.	5

1	structure to site		Protective gloves and safety goggles to be worn. Create level walkway to work area. Remove obstacles from path.	5
	Placement of reinforced structure on site and insertion of stools	Reinforced structure can cause trips/ falls.	Protective gloves to be worn. Caution must be exercised when walking over reinforced structure. Foothold must be selected carefully.	5