

## **POURING READY MIX CONCRETE**

RA NO

DATE

	•	
H.T.I Score 7		Medium-Regular Monitoring/ Supervision
Contract		
Persons involved in RA	Name	Signatures
Foreman		
Second Foreman		
Safety Officer		
Representative		

Documentation Required	Training Required	PPE and Safety Equipment Required
OHS Act and Construction Regulations	General induction - all employees	Long Trousers
Appointment 6(1)	Toolbox talks	Safety Gumboots
Appointments Plant/ Vehicle Operators	First Aider	Eve Protection
Appointment First Aider		Gloves
Competency Operator		
Competency First Aider		
Plant/ Vehicle registers		

	Activity Steps	Hazards and Risks	Preventative Measures	Rating
1	Positioning of truck on site	Persons in work area.Positioning truck too close to excavation/ structures/ material.Person can be run over and injured.  Truck can collapse the walls of the excavation or fall into it.  Structures or material can be damaged	Area to be cleared of personnel while truck is being positioned. Truck to have reverse warning hooter.  Spotter to be used to direct driver to correct position.	8
2	Positioning of chute	Sharp edges and snags on chute. Incorrect placement of chute. Injuries to personscuts, bruises, puncture wounds. Concrete poured in/ on wrong area.	Gloves to be worn. Competent person to position chute.	5

3	Pouring concrete		Gloves and eye goggles to be worn. Area to be cleared of all persons not directly involved in the pouring. Competent person to supervise the pouring. No loose clothing to be worn by operator. Persons to practise caution when in the vicinity of moving machinery/ parts.	8
---	------------------	--	--	---